

| ROOM FINISH SCHEDULE | | | | | | |
|--------------------------------------|------------------------|-----------|--------------|-------------------------|----------------|--|
| ROOM NO | ROOM NAME | BASE MATL | FLOOR FINISH | WALL FINISH | CEILING FINISH | COMMENTS |
| Basement - T.O. Slab | | | | | | |
| 001 | TEL COM | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 002 | STORAGE | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 003 | MECH | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 004 | LAUNDRY RM | RB1 | VF3 | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 005 | WIC | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 006 | ELEV. DISCONNECT | - | - | - | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 007 | STORAGE | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 008 | MECH | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 008A | VEST | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 009 | MECH | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 010 | JANITOR | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 011 | ELECTRICAL | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 012 | STORAGE | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 013 | STORAGE | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 014 | STORAGE | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 015 | PANTRY | CFS | VF3 | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| 016 | BASEMENT CORRIDOR | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| ST 01 | STAIR 1 | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| ST 03 | STAIR 3 | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| Ground FL. - T.O. Topping (264 09mm) | | | | | | |
| 101 | RESIDENT LOUNGE | RB1 | VF1 | PT1, WT2 | W02, PT6 | REFER TO DRAWING: A-600, WT2 @ BACKSPLASH ONLY. PT6 @ BULKHEAD ONLY |
| 102 | COMMUNITY ACCESS | RB1 | VF2 | PT1, WT2 | ACT1 | - |
| 103 | STAFF WC | RB1 | VF1 | PT1 | PT1 | - |
| 104 | JANITOR | RB1 | VF1 | PT1 | PT1 | - |
| 105 | MALE W.C. | WT4, WT5 | WT4, WT5 | WT3, WT4 | PT1 | WT4 (ACCENT APX 20%) |
| 105A | W.C. | WT4 | WT4 | WT3 | PT1 | - |
| 106 | OFFICE | RB1 | VF2 | PT1, PT2 | ACT1 | - |
| 107 | RECEP / ADMIN | RB1 | VF2 | PT1 | ACT1 | - |
| 108 | RECI-BIO CLST | VF1 | VF1 | PT1 | PT1 | - |
| 109 | ENTRY VESTIBULE | TB | FT1 | PT1 | PT1 | SEE A-500 FOR TILE BASE DETAIL |
| 110 | CORRIDOR | RB1 | VF1 | PT1, PT2, PT3 | PT1, ACT1 | REFER TO INTERIOR ELEVATIONS FOR PAINT LOCATIONS. REFER TO RCP FOR GWB/ACT TRANSITIONS |
| 111 | DINING HALL | RB1 | VF1 | PT, WT2 | W02, PT1, PT6 | PT1 @ GWB. PT6 @ GWB BULKHEAD |
| 112 | ELEVATOR | SEE SPEC | FT1 | SEE SPEC | SEE SPEC | SEE SPEC |
| 113 | KITCHEN | VF3, WCB | VF3 | WT3 | PT1 | - |
| 114 | MFG ROOM 1 | RB1 | VF2 | PT1 | ACT1 | - |
| 115 | UNIV. WC | PT1 | FT1 | PT1 | PT1 | - |
| 116 | OFFICE | RB1 | VF2 | PT1 | ACT1 | - |
| 117 | MFG ROOM 2 | RB1 | VF2 | PT1 | ACT1 | - |
| 118 | OFFICE | RB1 | VF2 | PT1 | ACT1 | - |
| FS1 | FS1 CORRIDOR | CFS | CO | PT1 | - | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE |
| ST 02 | STAIR 2 | RST | RST | PT1 | PT1 | REFER TO A-410 FOR PAINT LOCATIONS |
| 2nd FL. - T.O. Topping | | | | | | |
| 201 | SRO | RB1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 202 | SRO | RB1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 203 | SRO | RB1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 204 | SRO | RB1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 205 | WC SHOWERS | WCB | VF3 | WT3, WT4 | PT1 | WT4 (ACCENT APX 20%) |
| 206 | HARM REDUCTION SHELTER | RB1 | VF2 | PT1, PT2 | ACT1 | REFER TO INTERIOR ELEVATIONS FOR PAINT LOCATIONS. VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 207 | LANDING | RB1 | VF1 | PT1, PT3 | W02 | REFER TO INTERIOR ELEVATIONS FOR PAINT LOCATIONS. VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 208 | CONCILLI HALL | RB1 | VF1 | PT1 | PT1 | - |
| 208A | JAN | RB1 | VF1 | PT1 | PT1 | - |
| 209 | BF SRS | RB1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 210 | SRO | RB1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 211 | SRO | RB1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 212 | SRO | RB1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 213 | E.C. | - | CO | PT1 | PT1 | - |
| 213A | E.C. | - | CO | PT1 | PT1 | - |
| 304 | CORRIDOR | RB1 | VF1 | PT1 | ACT1 | - |
| 308 | STAIR 2 | RST | RST | PT1 | PT1 | REFER TO A-410 FOR PAINT LOCATIONS |
| 3rd FL. - T.O. Topping | | | | | | |
| 301 | SRO | RB1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 302 | SRO | RB1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 303 | SRO | RB1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 304 | SRO LAUNDRY | RB1 | VF2 | PT1, WT2 | PT1 | WT2 (BACKSPLASH), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 305 | WIC / SHOWERS | WCB | VF3 | WT3, WT4 | PT1 | WT4 (ACCENT APX 20%) |
| 306 | TRANSITIONAL SHELTER | RB1 | VF2 | PT1, PT2 | ACT1 | REFER TO INTERIOR ELEVATIONS FOR PAINT LOCATIONS. VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 307 | LANDING | RB1 | VF1 | PT1, PT3 | W02 | REFER TO INTERIOR ELEVATIONS FOR PAINT LOCATIONS |
| 309 | B.F. SRO | RB1, FT1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 310 | SRO | RB1, FT1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 311 | SRO | RB1, FT1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 312 | SRO | RB1, FT1 | VF2, FT1 | PT1, PT4, WT1, WT5, WT6 | PT1 | WT1 (BACKSPLASH), WT5 & WT6 (WIC UP TO 1300MM), WT6 (ACCENT APX 10%), VF2 TO HAVE EAST WEST GRAN DIRECTION |
| 313 | CORRIDOR | RB1 | VF1, W06 | PT1 | ACT1 | - |
| 313A | E.C. | - | CO | PT1 | PT1 | - |
| 313B | E.C. | - | CO | PT1 | PT1 | - |
| 314 | JAN | - | CO | PT1 | - | - |

| INTERIOR MATERIAL FINISHES | | | | |
|----------------------------|----------------------|--------------|--|---|
| FLOORS | | | | |
| CODE | FINISH | MANUFACTURER | DESCRIPTION | TYPICAL LOCATIONS |
| CO | POURED CONCRETE | --- | TROWEL FINISH CONCRETE W. SEALER | BASEMENT |
| VF1 | VINYL SHEET FLOORING | JOHNSONITE | ACCENT CONCRETE 2001 DARK GRAY | CORRIDORS, DINING HALL, LOUNGE, ENTRY VESTIBULE, ELEVATOR FLOOR |
| VF2 | VINYL SHEET FLOORING | ALTRO | ALTRO WOOD SMOOTH PALE BEECH-WSM2066 | OFFICES, DORMITORIES, SRO UNITS |
| VF3 | VINYL SHEET FLOORING | JOHNSONITE | GRANITE SAFE-T 699 ECLIPSE | KITCHEN, DORMITORY WASHROOMS, BASEMENT LAUNDRY, PANTRY |
| FT1 | PORCELAIN FLOOR TILE | OLYMPIA TILE | REGAL SERIES DARK GRAY MATTE 12" X 24" | SRO WASHROOMS, PUBLIC WASHROOMS, ELEVATOR, ENTRY VESTIBULE |
| RST | RUBBER STAIR TREAD | JOHNSONITE | RTR-XXX-RD, INTEGRATED STAIR TREADGRASS, RASSED ROUND TEXTURE, 192 TIDEWATER | CENTER STAIRWELL (FS2) |

| WALLS | | | | |
|-------|-------------------|----------------|------------------------------------|--|
| CODE | FINISH | MANUFACTURER | DESCRIPTION | TYPICAL LOCATIONS |
| PT1 | INTERIOR PAINT | BENJAMIN MOORE | WHITE DOVE DC-17 | ALL AREAS U.N.O. |
| PT2 | INTERIOR PAINT | BENJAMIN MOORE | LUCERNE AF-530 | CORRIDOR NICHS |
| PT3 | INTERIOR PAINT | BENJAMIN MOORE | FUJI AF-525 | CORRIDOR NICHS, HRST'S DORM PARTITION WALLS (OUTER SIDE) |
| PT4 | INTERIOR PAINT | BENJAMIN MOORE | SOLITUDE AF-545 | SRO ACCENT WALLS, HRST'S DORM PARTITION WALL (INNER SIDE) |
| PT5 | INTERIOR PAINT | BENJAMIN MOORE | MEDITERRANEAN TEAL 2123-10 | SRO CORRIDORS |
| PT6 | INTERIOR PAINT | BENJAMIN MOORE | WITCHING HOUR 2120-30 | KITCHENETTE BACKSPLASHES: KITCHENETTE, DINING HALL LOUNGE, DRINKING FOUNTAIN NICHE, AND SRO LAUNDRY LOUNGE |
| WT1 | CERAMIC WALL TILE | OLYMPIA TILE | PERWINKLE BRIGHT, 3"x6" | SRO BACKSPLASH, COMMUNITY ACCESS ROOM |
| WT2 | CERAMIC WALL TILE | OLYMPIA TILE | QUEBEC - BLACK FLECK, 2"x2" MOSAIC | KITCHENETTE BACKSPLASH: DINING HALL LOUNGE, DRINKING FOUNTAIN NICHE, AND SRO LAUNDRY LOUNGE |
| WT3 | CERAMIC WALL TILE | OLYMPIA TILE | WARM WHITE BRIGHT, 4"x20" | PUBLIC WASHROOMS, (FIELD COLOUR), KITCHEN |
| WT4 | CERAMIC WALL TILE | OLYMPIA TILE | CHARTREUSE BRIGHT, 4"x16" | PUBLIC WASHROOMS (ACCENT COLOUR) |
| WT5 | CERAMIC WALL TILE | DALTILE | PEPPER WHITE 0147, 4.25"x4.25" | SRO WASHROOMS (FIELD COLOUR) |
| WT6 | CERAMIC WALL TILE | DALTILE | GARDEN SPOT 0141, 4.25"x4.25" | SRO WASHROOMS (ACCENT COLOURS) |

| WALL BASE | | | | |
|-----------|----------------------------------|--------------|--|--|
| CODE | FINISH | MANUFACTURER | DESCRIPTION | TYPICAL LOCATIONS |
| RB1 | RUBBER BASE | JOHNSONITE | 20 CHARCOAL 4" TRADITIONAL TOELESS | ALL AREAS U.N.O., INCL. MILLWORK BASES, TYP. |
| RB2 | RUBBER BASE | JOHNSONITE | 20 CHARCOAL 6" TRADITIONAL TOELESS | HARM REDUCTION SHELTER PARTITIONS, TRANSITIONAL SHELTER PARTITIONS |
| WCB | PRE-FABRICATED WELDED COVE BASE | JOHNSONITE | CFS50 NEUTRAL COVE FILLER STRIP, EXTEND BASE 150mm LP WALL | DORM WASHROOMS, KITCHEN |
| TB | TILE BASE (PORCELAIN FLOOR TILE) | OLYMPIA TILE | REGAL SERIES DARK GRAY MATTE 12" X 24" | ENTRY VESTIBULE, PUBLIC WASHROOMS |
| CFS | CONCRETE FLOOR SEALER | --- | BRING CONCRETE FLOOR SEALER UP 8" @ WALL BASE | BASEMENT, FIRE STAIR 1, FIRE STAIR 3 |

| CEILING | | | | |
|---------|-----------------------|----------------|-------------------------|--|
| CODE | FINISH | MANUFACTURER | DESCRIPTION | TYPICAL LOCATIONS |
| PT1 | INTERIOR PAINT | BENJAMIN MOORE | WHITE DOVE DC-17 | ALL GWB LOCATIONS, TYP. U.N.O. REFER TO RCP |
| ACT1 | ACOUSTIC CEILING TILE | ARMSTRONG | SEE ASSEMBLIES SCHEDULE | OFFICES, MEETING ROOMS, CORRIDORS, COMMUNITY ACCESS ROOM, SHELTERS |

| MILLWORK | | | | |
|----------|------------------------|--------------|--|---|
| CODE | FINISH | MANUFACTURER | DESCRIPTION | TYPICAL LOCATIONS |
| W03 | SOLID HARDWOOD (MAPLE) | --- | SOLID WOOD PLANK - SELECT GRADE, 18" X 1 1/4" CLEAR SEAL | CORRIDOR BENCHES, REFER TO MILLWORK DWGS. |
| QS | QUARTZ SURFACE | DUPONT | 3/4" ZODIAC COLOUR GRAPHITE | KITCHENETTE COUNTERTOPS, TYP. |
| MEL1 | MELAMINE | UNIBOARD | CANADIAN GREY 168 | CABINET INTERIORS, TYP. |
| PL1 | PLASTIC LAMINATE | ARBORITE | S-613 CA DENIM BLUE | MILLWORK BASE & UPPER CABINETS IN SRO UNITS, REFER TO MILLWORK DWGS. |
| PL2 | PLASTIC LAMINATE | FORMICA | COLOR CORE2 912C-58 STORM, MATTE FINISH | MILLWORK BASE & UPPER CABINETS IN PUBLIC AREAS, REFER TO MILLWORK DWGS. |
| PL3 | PLASTIC LAMINATE | NEVMAR | PHANTOM GRAY MATRIX, MR800T1, TEXTURED | SRO UNIT COUNTERS, CLIENT LAUNDRY COUNTER, REFER TO MILLWORK DWGS. |

| VINYL | | | | |
|-------|---------------------|--------------|--|--|
| CODE | FINISH | MANUFACTURER | DESCRIPTION | TYPICAL LOCATIONS |
| FLM1 | VINYL FILM, FROSTED | 3M | VISTA SH20V1 | VISION STRIPS AT INTERIOR SCREENS AND FULLY GLAZED DOORS |
| FLM2 | VINYL FILM, OPAQUE | 3M | SCOTCHICAL ELECTROCUIT FILM SERIES T725, COLOUR - BRIGHT YELLOW 15 | SRO ROOM NUMBERS (WALLS, HM FRAMES AND DOORS) |

| FINISH NOTES: | |
|---------------|---|
| 1. | ALL EXPOSED MTL DECKING, DUCTWORK, TO BE PAINTED PT1 UNLESS OTHERWISE NOTED. |
| 2. | PROVIDE PAINT FINISH ON ALL GWB. |
| 3. | REFER TO PLANS AND INTERIOR ELEVATIONS FOR COMPLETE EXTENT OF LOCATION OF FINISHES. |
| 4. | PROVIDE PAINT FINISH ON ALL HM SCREENS OR DOOR FRAMES. |
| 5. | PROVIDE CLEAR SEAL ON ALL WOOD SILLS AND FINISH WOOD WORK. |
| 6. | ALL EXPOSED MECHANICAL GRILLES ARE TO BE PAINTED, ALLOW FOR COLORS TO BE DETERMINED BY ARCHITECT. |
| 7. | PROVIDE THRESHOLDS AT ALL FLOOR FINISH TRANSITIONS. |
| 8. | ALL EXPOSED STRUCTURE TO BE PAINTED, COLOR TO BE SPECIFIED BY ARCHITECT. |

ISSUED FOR TENDER

ISSUE DATE: MARCH 23, 2018

| NO. | DATE | DESCRIPTION |
|-----|------------|------------------------|
| 4 | 2018/04/09 | ISSUED FOR ADDENDUM #3 |
| 3 | 2018/03/23 | ISSUED FOR TENDER |
| 2 | 2017/12/19 | ISSUED FOR PERMIT |
| 1 | 2017/03/22 | ISSUED FOR COSTING |

PROJECT:

BROCK MISSION MEN'S SHELTER

217 MURRAY STREET, PETERBOROUGH, ONTARIO

DRAWING TITLE:

ROOM & FINISH SCHEDULE

PROJECT NO: 14276
SCALE: 1 : 20
DRAWN BY: XH
REVIEWED BY: JL

DRAWING NO:

A-006